


1 2 3 4 5 6 7 8

A

A



Scale 1:100

**NOTES**


1. ALL DIMENSIONS IN MILLIMETERS (mm) UNLESS OTHERWISE NOTED.
2. ALL CHANGES IN DIRECTION OF COMMS CONDUIT ACHIEVED USING LONG RADIUS SWEEPING BENDS.
3. LONG RADIUS SWEEPING BENDS CAN EITHER BE MADE UP FROM BENDING CONDUIT LENGTHS OR AS SPECIFIED ON ROUTE DESIGN IN COMPLIANCE WITH NS234.
4. WHEN LAYING CONDUITS, ENSURE CLEARANCE FROM CONDUIT SPACER BRACKETS.
5. WARNING TAPE TO DISPLAY "DANGER - ELECTRIC CABLES BELOW"
6. WARNING TAPE TO BE ABOVE COMMS CONDUIT FOR ENTIRE LENGTH WHERE CONDUIT DEVIATES FROM HV CONDUIT NEST
7. DIVERSITY OF COMMUNICATIONS CONDUITS TO BE MAINTAINED AT ALL TIME.
8. ALL CONDUIT ENTRIES NOT BEING UTILISED TO BE FILLED WITH GROUT
9. CONDUITS TO ENTER PIT FROM CENTRE BELLMOUTHS FIRST, THEN WORKING OUT TOWARDS THE SIDE AS REQUIRED.
10. COMMS PIT TO BE RATED MIN CLASS D, LID TO BE IN ACCORDANCE WITH NS172

B

B

C

C



SECTION 1  
SCALE 1:25

D

D

E

E

F

F

CAD DRAWING  
 DO NOT MANUALLY AMEND  
 AMENDMENTS

NETWORK STANDARD  
  
 COMMUNICATIONS ENGINEERING  
 145 NEWCASTLE RD  
 WALLSEND 2287

SCALE	AS SHOWN
DESIGNED	A.FREESTONE
DRAWN	A.FREESTONE
CHECKED	
APPROVED	A.LLOYD
DATE	11/01/2017
PROJECT NUMBER	STD
PROJTRAK NUMBER	

<b>AUSGRID FIBRE NETWORK          FIBRE &amp; DUCT ARRANGEMENT          IN ROAD COMMS PIT</b>			
SIZE	DRAWING No	SHEET	AMD
A3	212393	19	0

20111014

1 2 3 4 5 6 7 8

©